West Seattle and Ballard Link Extensions

Mercer Stakeholders 6/22/2023





Why we're here today

 Brief recap of May status report to Board on Denny Station

 Overview of current activities in anticipation of July status report to Board

Environmental process next steps

- West Seattle and Ballard Link Extensions Draft EIS was published in January 2022
- Both extensions were initially on the same environmental review timeline
- Additional environmental review needed for project refinements for Ballard Link Extension resulting from Board action in March 2023
- Environmental review for the two extensions will now proceed on different timelines
 - West Seattle Link Extension will proceed to a Final EIS
 - Ballard Link Extension will require a SEPA Supplemental Draft EIS/NEPA Draft EIS
 (incorporating all work to date including previous comments, public outreach and environmental analysis)





March Board action

Motion No. M2023-18


While the previously-identified preferred alternative is not modified at this time, staff is directed to carry forward both the Denny Station on Westlake (DT1) Draft EIS Station alternative and Denny Station on Terry (i.e. South Lake Union Mix and Match) alternative as part of ongoing environmental review. Staff is directed to continue collaboration with City of Seattle and community partners to further clarify the technical, financial, schedule and risk implications of both alternatives and return to the Board with a status report by May 25, 2023.

Recap of May status report

Work sessions

- Over 20 technical work sessions since Board action in March to clarify technical and other implications and look for ways to minimize impacts
- Topics included utilities (including electrical, fiber optic/telecom, sewer, etc.), constructability, construction schedule, roadway closures, cost
- For Denny/Terry, assessed potential to detour fiber infrastructure off Terry
 Ave and potential modifications to the carrier hotel in that area
- For Denny/Westlake, examined potential refinements to the station location to reduce effects to Westlake Ave including:
 - Shifting the station north to allow traffic to be maintained on Westlake Ave during construction
 - Shifting the station west onto private property to avoid Westlake Ave

Denny Westlake **Draft EIS DT-1**







Denny Terry **SLU Mix-Match**

\$340m additional cost

Uncertainty of fiber relocation could delay overall schedule


Substantial disruption and litigation risk if inadvertently cut fiber lines

Westlake Ave open to cars, buses and streetcar during construction South Lake Westlake Ave N Union Extensive ground improvement/ mined cavern on Harrison St (east of Dexter) Minimal impact to ridership; short walk to transit lines on Westlake Ave; provides DENNY station access to both sides More extensive electrical of Denny Way utilities on Harrison St 1/8 mi Major relocation of fiber from 1/4 mi Terry Ave onto adjacent streets (Boren, Denny) **SoundTransit**

Tunnel








Denny Westlake Shifted North

\$170m additional cost*

Phased in-street construction to maintain traffic adds construction complexity and extends duration of street effects (8 years vs 4 years)





Tunnel




Station



Denny Westlake Shifted West

- To further avoid impacts to Westlake Ave, shifted station west out of street right of way onto private property
- Resulted in very close spacing to Harrison St station with geometric and technical constraints
- Hence, considered consolidated station concept instead of two closely spaced stations



Denny Westlake Shifted West

\$440m cost savings due to consolidation of Denny and Harrison St stations*

Potentially shorter station construction duration due to improved site access and mostly off-street construction

Ridership, transit integration and passenger experience implications of consolidated station to be further assessed


.

Tunnel



Station








Lower Higher performing	Denny Westlake	Denny Terry	Denny Westlake refinement options	
	Draft EIS (DT-1)	SLU Mix-Match	Shifted North	Shifted West
Technical street closures	Westlake Ave fully closed to cars, buses and streetcar for 4 years during construction	Westlake Ave open to cars, buses and streetcar during construction	Westlake Ave temporarily decked during construction. Open to cars and buses but not streetcar. Reduced number of lanes for 3-4 years.	Westlake Ave substantially open to cars, buses and streetcar during construction; avoids closure of Harrison St
utilities	Sewer and electrical utilities on Westlake Ave; fiber crossing at Lenora St; major electrical utilities on Harrison St	Major relocation of fiber from Terry Ave onto adjacent streets (Boren, Denny); more extensive electrical utilities on Harrison St	Less extensive sewer and electrical utility work on Westlake Ave; avoids fiber crossing at Lenora St; major electrical utilities on Harrison St	Substantially avoids utilities on Westlake Ave and completely avoids major electrical utilities on Harrison St
constructability	Base case for constructability comparison	Extensive ground improvement/mined cavern on Harrison St (east of Dexter)	Phased in-street construction to maintain traffic adds construction complexity and extends duration of street effects (8 years vs 4 years)	Potentially shorter station construction duration due to improved site access and mostly off-street construction
Performance ridership, transit integration, passenger experience	Convenient transfer to transit on Westlake Ave	Minimal impact to ridership; short walk to transit lines on Westlake Ave; provides station access to both sides of Denny Way	Convenient transfer to transit on Westlake Ave	To be assessed
Cost compared to Denny Westlake Draft EIS DT-1	Base case for cost comparison	\$340m additional cost	\$170m additional cost*	\$440m cost savings due to consolidation of Denny and Harrison St stations*
Schedule overall project delay	Base case for schedule comparison	Uncertainty of fiber relocation could delay overall schedule	No delay to overall schedule	No delay to overall schedule
Risk substantial cost, schedule, or feasibility risks	Base case for risk comparison	Substantial disruption and litigation risk if inadvertently cut fiber lines	Potential property development risk	Potential property development risk; avoids major electrical utilities on Harrison St
All costs are rounded in \$2019. Comparative estimates				




Current activities











E line

Route 5

Downtown-Fremont-Greenwood


Route 62

Downtown-Wallingford-Sand Point

Route 8/11
Interbay-Capitol Hill-Madison Park


- Bus-rail transfers are about 32% of total boardings at South Lake Union Station;
 12% at Denny Station
- 80% of all bus-rail transfers related to four routes


Daily Transfer Boardings to Link From Buses at SLU Station











Next steps

Next steps

- Complete assessment of ridership and transit integration solutions
- Engagement on assessment results in mid July
- Return to the Board with a status report and potential board action in late July

wsblink.participate.online 206-903-7229





